NOTICE: ALL LANDOWNERS, DEVELOPERS AND CONTRACTORS

FAILURE TO COMPLY WITH THE CONSTRUCTION PROCEDURE REQUIREMENTS LISTED BELOW MAY RESULT IN THE COSTLY REMOVAL OF STRUCTURES, TIME DELAYS OR THE ISSUANCE OF A STOP WORK ORDER.

CONSTRUCTION PROCEDURE REQUIREMENTS

1. RIGHT-OF-WAY EXCAVATION PERMIT - PRIOR TO THE COMMENCEMENT OF ANY DIGGING, ALTERATION OR CONSTRUCTION WITHIN THE PUBLIC RIGHT-OF-WAY (STREETS, ALLEYS, PUBLIC EASEMENTS), A RIGHT-OF-WAY EXCAVATION PERMIT SHALL BE APPLIED FOR AND OBTAINED BY THE CONTRACTOR FROM THE CITY OF

2. LAND DISTURBANCE PERMIT - AN APPROVED EROSION AND SEDIMENT CONTROL PLAN FOR ANY BORROW/FILL SITES ASSOCIATED WITH THE PROJECT MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A LAND DISTURBANCE PERMIT.

3. PLANS AND PERMITS - A COPY OF THE PLANS AS APPROVED BY THE CITY (SIGNED BY THE PROPER CITY OFFICIALS) AND ALL PERMITS ISSUED BY THE CITY SHALL BE AVAILABLE AT THE CONSTRUCTION SITE AT ALL TIMES OF ONGOING CONSTRUCTION.

4. LOCATION OF UTILITIES - THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION.

5. CONSTRUCTION ENTRANCE - THE CONTRACTOR SHALL INSTALL AN ADEQUATE CONSTRUCTION ENTRANCE FOR ALL CONSTRUCTION RELATED EGRESS FROM THE SITE. SIZE AND COMPOSITION OF CONSTRUCTION ENTRANCE SHALL BE AS SHOWN

6. STREETS TO REMAIN CLEAN - IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO INSURE THAT THE PUBLIC STREET ADJACENT TO THE CONSTRUCTION ENTRANCE REMAINS FREE OF MUD, DIRT, DUST, AND/OR ANY TYPE OF CONSTRUCTION MATERIALS OR LITTER AT ALL TIMES.

7. BARRICADES/DITCHES - THE CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF ALL EXCAVATED DITCHES AND SHALL FURNISH AND ENSURE THAT ALL BARRICADES PROPER AND NECESSARY FOR THE SAFETY OF THE PUBLIC ARE IN PLACE.

8. SEWER AND PAVEMENT REPLACEMENT - CONSTRUCTION OF SANITARY SEWERS AND THE REPLACEMENT OF PAVEMENT SHALL BE IN ACCORDANCE WITH APPROVED STANDARDS AND SPECIFICATIONS OF THE CITY OF ROANOKE AND THE WESTERN VIRGINIA WATER AUTHORITY

9. APPROVED PLANS/CONSTRUCTION CHANGES - ANY CHANGE OR VARIATION FROM CONSTRUCTION DESIGN AS SHOWN ON THE OFFICIALLY APPROVED PLANS SHALL BE APPROVED BY THE EROSION AND SEDIMENT CONTROL AGENT PRIOR TO SAID CHANGES OR VARIATION IN CONSTRUCTION BEING MADE.

10. FINAL ACCEPTANCE/CITY - THE OWNER OR DEVELOPER SHALL FURNISH THE CITY OF ROANOKE'S PLANNING BUILDING AND DEVELOPMENT DEPARTMENT WITH A FIELD SURVEYED FINAL CORRECT SET OF AS-BUILT PLANS OF THE NEWLY CONSTRUCTED STORM RAIN AND/OR STORMWATER MANAGEMENT FACILITIES PRIOR TO FINAL ACCEPTANCE AND ISSUANCE OF A CERTIFICATE OF OCCUPANCY BY E CITY. AS-BUILT PLANS SHALL BE PROVIDED IN THE STATE PLANE VIRGINIA SOUTH COORDINATE SYSTEM, NAD 1983, FIPS 4502 FEET, US SURVEY FEET, DATUM NA

83, IN THE FORM OF 1 PAPER COPY AND 1 DIGITAL AUTOCAD FILE.

REMOVE AND REPLACE THE FRONT FACADE OF BUILDING 623 GILMER AVE. NW

ROANOKE, VIRGINIA

SITE ADDRESS 623 GILMER AVE. NW ROANOKE, VIRGINIA 24016

> **ENGINEER CONTACT** LMW P.C.

ENGINEERING - ARCHITECTURE - SURVEYING - LANDSCAPE DESIGN CONTACT PERSON: DOUGLAS R MEREDITH JR., P.E., L.L.S.

EMAIL: dmeredith@lmwpc.net

Washington Strasbur FAIRFAX AVE Staunton Charlottesville **VICINITY MAP** NO SCALE Lynchburg Roanoke Petersburg **Blacksburg Newport News** Wytheville J Emporia – Portsmoutl

VIRGINIA LOCATION MAP

NO SCALE

INDEX OF DRAWINGS

2. T-1 ABBREVIATIONS, LEGEND, & GENERAL NOTES 3. T-2 EROSION & SEDIMENT CONTROL SHEET

4. C-1 SITE PLAN

5. D-1 DEMOLITION 6. S-1 ELEVATIONS

7. S-2 DETAIL PLAN

8. S-3 WALL DETAILS

PROPERTY OWNER:

LMW PROFESSIONAL CORPORATION 102 ALBEMARLE AVE., S.E.

ROANOKE, VIRGINIA 24013 (540) 345-0675


TAX#: 2011102 LEGÄL REFERENCE: PT LOT 3 BLK 17 RF&H

ZONING CLASSIFICATION: RM-1 OVERLAY DISTRICT: NDD PROPOSED USE OF SITE: NO CHANGE

ROANOKE CITY USE ONLY









Lic No.22942

Architecture Surveying Landscape Design

www.lmwpc.net ph: 540.345.0675 fax: 540.342.4456 Imweng@Imwpc.net

REMOVE AND REPLACE THE FRONT FACADE OF BUILDING 623 GILMER AVE. NW

COMM.NO.: 4228 DATE: 08/26/14 SET NO.: _____

| PROJECT REVISION | | | |
|------------------|------|-------------|----|
| | | | |
| | | | |
| | | | |
| | | | |
| No. | Date | Description | Ву |

LEGEND / SYMBOLS LEGEND / SYMBOLS **ABBREVIATIONS** POINT ON TANGENT ABANDON, ABANDONED FLARED END SECTION GYPSUM DRYWALL ROUGH WOOD EXISTING NEW DESCRIPTION ABV FLEX FLEXIBLE PVC ABOVE POLYVINYL CHLORIDE AFF ABOVE FINISH FLOOR FL FLOOR PORCELAIN TILE FINISH WOOD <u>CONCRETE</u> ABUT FCO FLOOR CLEAN-OUT PSF ABUTMENT POUNDS PER SQUARE FOOT ACM ASBESTOS CONTAINING MATERIAL FD FLOOR DRAIN PSI POUNDS PER SQUARE INCH CONCRETE MASONRY UNIT <u>PLYWOOD</u> BUILDING WITH PORCH OR STOOP ACT FT FOOT PP ACOUSTIC CEILING TILE POWER POLE FTG FOOTING PAIR ADJ ADJACENT PR _____ **BATT INSULATION** <u>BRICK</u> AGGR AGGREGATE FDN FOUNDATION PT PRESSURE TREATED FOUNDATION ONLY FAI PROJ AHU AIR HANDLING UNIT FRESH AIR INTAKE PROJECTION RIGID INSULATION ALT ALTERNATE **FUTURE** PUE PUBLIC UTILITY EASEMENT /--35___ _____35 _____ CONTOUR, CONTOUR WITH ELEVATION GAGE Q TILE ALUM ALUMINUM QUARRY TILE 20.0 E OR *^\ ADA AMERICANS WITH DISABILITIES ACT 20.0 OR X 1025 GALLON RAD RADIUS SPOT ELEVATION GPH ANC GALLONS PER HOUR RR RAILROAD ANCHOR GALLONS PER MINUTE GPM REC RECORD ANOD ANODIZED ====== CONCRETE CURB APPROX APPROXIMATE GALV GALVANIZED RDCR REDUCER TYPICAL SYMBOLS ====== GAR GARAGE REF REFERENCE AUDIO VISUAL CONCRETE CURB & GUTTER _____ GAS REFRIG REFRIGERATION BASE LINE GATE VALVE BEGIN VERTICAL CURVE ELEVATION REINF BVCE REINFORCE(D) CONCRETE WALK OR SLAB BVCS BEGIN VERTICAL CURVE STATION GLASS RCP REINFORCED CONCRETE PIPE BEG BEGIN, BEGINNING GOVT GOVERNMENT REBAR REINFORCING BAR PAVEMENT GRTG GRATING BJ BELL JOINT REL RELOCATED PLAN OR DETAIL SYMBOL _ _ _ _ _ GR _____ BEL BELOW GRAVEL REQD REQUIRED UNPAVED OR GRAVEL ROAD _ _ _ _ _ GRV GRAVITY ROOF VENT _____ ВМ BENCH MARK REV REVISION BTW GND BETWEEN GROUND RT RIGHT CONSTRUCTION EASEMENT BITUMINOUS GFI GROUND FAULT INTERRUPTER R/W RIGHT OF WAY BSP GWB BLACK STEEL PIPE GYPSUM WALL BOARD ROAD PERMANENT EASEMENT _____ _..__._ HANDICAPPED ACCESSIBLE BOC HC BOTTOM OF CURB RD ROOF DRAIN **BUILDING SECTION** BOS HDWR BOTTOM OF STEP HARDWARE RTU ROOF TOP UNIT $\bigcirc \bigcirc \bigcirc \bigcirc$ TREE LINE BOW HDWD BOTTOM OF WALL HARDWOOD WALL SECTION OR RM ROOM Α4 BRDG ΗE HIGH EFFICIENCY OR BRIDGING OR R RO ROUGH OPENING OR ELEVATION SYMBOL TREE OR SHRUB BTU BRITISH THERMAL UNIT HVAC HEATING VENTILATING & AIR RTE ROUTE BTUH BTU PER HOUR CONDITIONING R TILE RUBBER TILE ___ × ____ × -___ × ____ × -FENCE (EXISTING OR PROPOSED NOTED) BLDG BUILDING HEIGHT SAN SANITARY HPT HIGH POINT BV BUTTERFLY VALVE SS SANITARY SEWER CENTERLINE CREEK, SWALE, DITCH PLAN OR DETAIL SYMBOL CAPY CAPACITY НМ HOLLOW METAL SO SASH OPENING CPT CARPET HS HOOK STRIP SCHED SCHEDULE PROPERTY LINE CAST IRON HORIZ HORIZONTAL SECT SECTION CLG CEILING НА HOSE BIBB SER SERVICE CENTERLINE OR BASELINE — £ —— Ĕ — CTR HR CENTER HOUR SH SHEET CENTER LINE H&T HUB AND TAC S/W SIDEWALK CERAMIC TILE HWHOT WATER SÍM SIMILAR \triangle FIELD SURVEY TRAVERSE POINT -SHEET NUMBER WHERE CLEANOUT HYD **HYDRANT** CO SE SLOPE EASEMENT ELEVATION IS DRAWN CLR CLEAR INCH SC SP 0 SOLID CORE P.C. OR P.T. NORTH ARROWS COLD WATER INSIDE DIAMETER CW SPACE COL COLUMN INSUL INSULATION SPEC SPECIFICATION GEOLOGIC BORE HOLE COMB COMBINATION INV INVERT SQ SSTL SQUARE CONC CONCRETE IRON PIN (FOUND OR SET NOTED) STAINLESS STEEL BENCH MARK (EXISTING OR SET NOTED) CMU CONCRETE MASONRY UNIT JOINT STD STA STANDARD COND CONDENSER/CONDUIT JUNCTION STATION CND KILOVOLT AMPS STL STOR STORM DRAIN AND ENDWALL CONDUIT KVA STEEL CONN CONNECTION ΚW KILOWATT STORAGE INTERIOR ELEVATION SYMBOL CONST CONSTRUCTION LAM LAMINATE SD SANITARY SEWER STORM DRAIN CONT CONTINUOUS LVL LAMINATED VENEER LUMBER STR STREET CONTR CONTRACTOR LENGTH, LONG STRUCT FORCE MAIN STRUCTURAL CONTROL JOINT LIGHT SUR SURVEY LIGHT POLE CONV CONVEYOR SUSP SUSPENDED GAS MAIN OR SERVICE LINE COR LINEAL FOOT CORNER SW SWITCH CMP LINEAR CORRUGATED METAL PIPE LIN WATER MAIN OR SERVICE LINE SYM SYMMETRIC(AL) CR STONE LONG CRUSHED STONE SYS SYSTEM LONG RADIUS CF CUBIC FOOT TEL OVERHEAD ELECTRICAL LINE TELEPHONE CFM CUBIC FOOT PER MINUTE MAIL BOX TP TELEPHONE POLE CULV CULVERT МН MANHOLE TV TELEVISION OVERHEAD TELEPHONE LINE MFR CURB AND GUTTER MANUFACTURER **TEMP TEMPORARY** DEPTH OR DEGREE OF CURVE MAS MASONRY **TSTAT THERMOSTAT** ____UE____ UNDERGROUND ELECTRICAL LINE DTL MCJ MASONRY CONTROL JOINT THK THICK DOOR DESIGNATION DIAG DIAGONAL МО MASONRY OPENING THRU THROUGH UNDERGROUND TELEPHONE LINE MATL DIAMETER MATERIAL T & B TOP AND BOTTOM MAX DIFF DIFFUSER(S) MAXIMUM TOC TOP TOS PIPE FITTINGS MECH MECHANICAL DIM DIMENSION TOP OF PAVEMENT WINDOW DESIGNATION MECHANICAL JOINT DISC ΜJ DISCONNECT TOP OF STEP FIRE HYDRANT MFISS MEDIUM FISSURE DIV DIVISION TOW TOP OF WALL MBH MEGA BTU PER HOUR DBL DOUBLE TPO THERMOPLASTIC POLYOLEFIN GATE VALVE MTL METAL DEMOLITION DESIGNATION DN DOWN TR TREAD MIN MINIMUM DOWNSPOUT TRTD TREATED CLEANOUT MBL MINIMUM BUILDING LINE DRAINAGE EASEMENT TS TUBULAR STEEL MISC DWG DRAWING MISCELLANEOUS TYP TYPICAL STORM DRAIN SEWER MANHOLE ACM DESIGNATION MON MONUMENT DW DRIVEWAY UND UNDER MTD DROP INLET, DUCTILE IRON MOUNTED DI UG UNDERGROUND NAIL AND CAP SANITARY SEWER MANHOLE DMH N & C DROP MANHOLE UNDERWRITERS LABORATORY UL NEUT NEUTRAL DWL DWELLING UNIFORM FEDERAL ACCESSIBILITY UFAS NOM NOMINAL DROP INLET (CURB AND GRATING TYPES) EΑ FACH STANDARDS NPW EACH WAY, ENDWALL NON POTABLE WATER ΕW USC&GS UNITED STATES COAST AND NA NOT APPLICABLE ESMT EASEMENT WM - WATER METER GEODETIC SURVEY

DWM - DOUBLE WATER METER

POWER POLE, GUY AND ANCHOR

LIGHT POLE

PAVED DITCH

TELEPHONE PEDESTAL

STEEL ENCASEMENT

CONCRETE ENCASEMENT

ABANDON OR REMOVE

LIMITS OF CONSTRUCTION

BURIED TELEPHONE VAULT

 \rightarrow

PROFILE

PROFILE PLAN

4 4 1

T

`\----

ノーーーへ

`**≻**----(

PROFILE PLAN

PROFILE PLAN

— *ШШШШ* —

T.

TELEPHONE POLE, GUY AND ANCHOR

CULVERT WITH FLARED END SECTION

AIR RELEASE VALVE / VAULT ASSEMBLY

BLOW OFF VALVE / VAULT ASSEMBLY

NIC

NTS

OPP

ОН

OD

OVHD

OFCI

OFOI

PVMT

PAV

PED

PERF

PER

PERP

PLAM

PLYWD

PL

PCC

РC

PRC

PT

PVI

POL

NO

EBL

EWC

ELEC

ELEV

ENCL

EOL

EVCE

EVCS

ENGR

ENTR

EQ

EQPT

EVAP

EXH

EXG

EXP

EXP ST

EΑ

EXT

FΒ

FOS

FIG

FF

FIN

FF

FEC

FTRD

FLG

EASTBOUND LANE

ELECTRICAL

ELEVATION

ENGINEER

ENTRANCE

EQUIPMENT

EXHAUST

EXISTING

EXTERIOR

FIGURE

FLANGE

FACE BRICK

FACE OF STUD

FINISH FLOOR

FIRE TREATED

FINISHED FLOOR

FIRE EXTINGUISHER CABINET

FINISH(ED)

EXPANSION

EVAPORATIVE(OR)

EXPANSION JOINT

EXPOSED STRUCTURE

EQUAL

END OF LINE

EDGE OF PAVEMENT

ENCLOSE/ENCLOSURE

ELECTRIC WATER COOLER

END VERTICAL CURVE ELEVATION

END VERTICAL CURVE STATION

NOT IN CONTRACT

NOT TO SCALE

ON CENTERS

OPPOSITE HAND

OUTSIDE DIAMETER

OWNER FURNISHED CONTRACTOR

OWNER FURNISHED OWNER

NUMBER

OPPOSITE

OVER ALL

OVERHEAD

INSTALLED

INSTALLED

PAINTED

PAVEMENT

PEDESTRIAN

PERFORATED

PERPENDICULAR

PLASTIC LAMINATE

POINT OF CURVE

POINT ON LINE

PLATE, PROPERTY LINE

POINT OF INTERSECTION

POINT OF TANGENCY

POINT OF REVERSE CURVE

POINT OF COMPOUND CURVE

POINT OF VERTICAL INTERSECTION

PERIMETER

PLYWOOD

PAVING

UON

VVAL

VAR

VTR

VERT

VC

VSD

VCT

VWC

VDOT

VUSBC

VOL

WC

WR

WS

WP

WT

WBL

WVWA

WDW

W/O

WVDH

UNLESS OTHERWISE NOTED

VENT THROUGH ROOF

VERTICAL SIGHT DISTANCE

VINYL COMPOSITION TILE

VIRGINIA DEPARTMENT OF

CONTROL REGULATIONS

VIRGINIA EROSION AND SEDIMENT

VIRGINIA UNIFORM STATEWIDE

WEST VIRGINIA DEPARTMENT OF

WIDE FLANGE, WIDE, WASTE, WATER

WESTERN VIRGINIA WATER

VINYL WALL COVERING

VERTICAL CURVE

TRANSPORTATION

BUILDING CODE

WATER CLOSET

WATER RESISTANT

WATER SURFACE

WESTBOUND LANE

WEATHERPROOF

WATER LINE

VOLUME

WEIGHT

HIGHWAYS

AUTHORITY

WET BULB

WINDOW

WITHOUT

WOOD

WITH

VALVE, VENT

VARIABLE

VERTICAL

DOUGLAS R. MEREDITH, JR Lic No.22942 20, 2-19-15 STONAL ENGINEERS

Drawn By Checked By RCW 08/26/14

4228 Drawing Commission No.

2 of Sheet

02 Albemai Roanoke, `

P.C.



3 Z

H

ONT FR THE DING REPLACE OF BUILT INTER AVE.

FACADE 623 GIL VE. 0 REM

EROSION & SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION

The purpose of this project is to demolish the front facade and replace it with a new facade.

EXISTING SITE CONDITIONS

The proposed site is located on approximately 0.0739 acres that is located on the north side of Gilmer Ave. and, east side of 7th ST. and South of Moorman Ave., in the Roanoke, VA.

ADJACENT AREAS

The project site is bordered to the north by Mooreman Street, to the east by 7 th St. and to the south Gilmer Ave.

STRUCTURAL PRACTICES

- 1. Safety Fence (Section 3.01) A protective barrier installed to prevent access to an erosion control measure and to prohibit the undesirable use of an erosion control measure by the public.
- 2. Temporary Seeding (Section 3.31) Temporary seeding will be placed on all disturbed areas that will not be brought to final grade within one year or less. Temporary seeding will aid in the reduction of dust and sediment. Temporary seeding will be

Sept. 1 — Feb. 15 50/50 Mix of Annual Ryegrass 50—100 (lbs./acre) Feb. 16 - Apr. 30 Annual Ryegrass 60-100 (lbs./acre) May 1 - Aug. 31 German Millet 50 (lbs./acre)

3. Permanent Seeding (Section 3.32) After final grading permanent seeding will be employed to reduce erosion and sediment yield.

> General Slope (3:1 OR LESS) Kentucky 31 Fescue 128 lbs. Red Top Grass 2 lbs. Seasonal Nurse Crop* 20 lbs. 150 lbs. Low-Maintenance Slope (Steeper than 3:1) Kentucky 31 Fescue 108 lbs. Red Top Grass 2 lbs. Seasonal Nurse Crop* 20 lbs. Crownvetch** 20 lbs.

*Use seasonal nurse crop in accordance with seeding dates as stated below:

150 lbs.

March, April through May 15th Annual Rye May 16th through August 15th Foxtail Millet August 16th through September, October Annual Rye November through February Winter Rye

**If Flatpea is used, increase to 30 lbs./acre. All legume seed must be properly inoculated. Weeping Lovegrass may also be included in any slope or low-maintnance mixture during warmer seeding periods; add 10-20 lbs/acre in mixes

- 4. Mulching (Section 3.35) Application of plant residues or other suitable materials to the soil surface to prevent erosion by protecting the soil surface from raindrop impact and reducing the velocity of overland flow; to foster the growth of vegetation by increasing available moisture and providing insulation against extreme heat and cold. Areas which have been permanently seeded should be mulched immediately following seeding.
- 5. Tree Preservation and Protection (Section 3.38) Protection of desirable trees from mechanical and other injury during land disturbing and construction activity.
- 6. Dust Control (Section 3.39) If arid conditions prevail dust control practices will be employed as required.

- 1. Construction should be sequenced so that grading operations can begin and end as quickly as possible.
- 2. Erosion and Sediment control devices shall be installed as the first step of construction.
- 3. Areas which are not to be disturbed shall be clearly marked by flags, signs,
- 4. The grading contractor shall be responsible for the installation and maintenance of all erosion and sediment control practices. Inspections are to be made periodically and after every significant rainfall.
- 5. After achieving adequate stabilization, the temporary E&S controls will be cleaned up and removed, and the sediment basins will be cleaned out and converted to permanent stormwater management basins.

PERMANENT STABILIZATION

All areas disturbed by construction shall be stabilized with permanent seeding immediately following finish grading. Seeding shall be done with Kentucky 31 Tall Fescue according to Std. & Spec. 3.32, PERMANENT SEEDING, of the handbook. Erosion control blankets will be installed over fill slopes which have been brought to final grade and have been seeded to protect the slopes from rill and gully erosion and to allow seed to germinate properly. Mulch (straw or fiber) will be used on relatively flat areas. In all seeding operations, seed, fertilizer and lime will be applied prior to mulching.

In general, all erosion and sediment control measures will be checked daily and after each significant rainfall. Any items not found in accordance with the Virginia Erosion and Sediment Control Handbook will be immediately replaced and/or repaired. The following items will be checked in particular:

- 1. The silt fence barrier will be checked regularly for undermining or deterioration of the fabric. Sediment shall be removed when the level of sediment deposition reaches half way to the top of the barrier.
- 2. The seeded areas will be checked regularly to ensure that a good stand is maintained. Areas should be fertilized and re—seeded as needed.

The erosion and sediment control measures shown on the construction plans are the minimum measures required. Due to construction phasing and other considerations all measures can not be shown. The owner, through his contractor, will employ whatever measures which may be required to assure that sediment laden runoff does not leave the site.

All materials and measures employed for erosion and sediment control will be in accordance with the Virginia Erosion and Sediment Control Handbook, latest

If, during construction, additional Erosion and Sediment Control measures are deemed necessary, they shall be installed as directed by the Owner, Engineer or County agent.

This project is to be constructed consistent with the 2013 Virginia Erosion And Sediment Control Regulations.

VESCH STATE MINIMUM STANDARDS (1992 EDITION)

An erosion and sediment control program adopted by a district or locality must be consistent with the following criteria, techniques and methods:

- 1. Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the site. Temporary soil stabilization shall be applied within seven days to denuded areas that may not be at final grade but will remain dormant for longer than 30 days. Permanent stabilization shall be applied to areas that are to be left dormant for more than one year. N/A
- 2. During construction of the project, soil stock piles and borrow areas shall be stabilized or protected with sediment trapping measures. The applicant is responsible for the temporary protection and permanent stabilization of all soil stockpiles on site as well as borrow areas and soil intentionally transported from the project site. N/A
- 3. A permanent vegetative cover shall be established on denuded areas not otherwise permanently stabilized. Permanent vegetation shall not be considered established until a ground cover is achieved that is uniform, mature enough to survive and will inhibit erosion. N/A
- 4. Sediment basins and traps, perimeter dikes, sediment barriers and other measures intended to trap sediment shall be constructed as a first step in any land-disturbing activity and shall be made functional before upslope land disturbance
- 5. Stabilization measures shall be applied to earthen structures such as dams, dikes and diversions immediately after
- 6. Sediment traps and sediment basins shall be designed and constructed based upon the total drainage area to be served by the trap or basin. <u>N/A</u>
- 6.1. a. The minimum storage capacity of a sediment trap shall be 134 cubic yards per acre of drainage area and the trap shall only control drainage areas less than three acres. N/A
- 6.2. b. Surface runoff from disturbed areas that is comprised of flow from drainage areas greater than or equal to three acres shall be controlled by a sediment basin. The minimum storage capacity of a sediment basin shall be 134 cubic yards per acre of drainage area. The outfall system shall, at a minimum, maintain the structural integrity of the basin during a 25-year storm of 24-hour duration. Runoff coefficients used in runoff calculations shall correspond to a bare earth condition or those conditions expected to exist while the sediment basin is
- 7. Cut and fill slopes shall be designed and constructed in a manner that will minimize erosion. Slopes that are found to be eroding excessively within one year of permanent stabilization shall be provided with additional slope stabilizing measures until the problem is corrected. N/A
- 8. Concentrated runoff shall not flow down cut or fill slopes unless contained within an adequate temporary or permanent channel, flume or slope drain structure. N/A
- 9. Whenever water seeps from a slope face, adequate drainage or other protection shall be provided. N/A
- 10. All storm sewer inlets that are made operable during construction shall be protected so that sediment-laden water cannot enter the conveyance system without first being filtered or otherwise treated to remove sediment. N/A
- 11. Before newly constructed stormwater conveyance channels or pipes are made operational, adequate outlet protection and any required temporary or permanent channel lining shall be installed in both the conveyance channel and receiving channel. <u>N/A</u>
- 12. When work in a live watercourse is performed, precautions shall be taken to minimize encroachment, control sediment transport and stabilize the work area to the greatest extent possible during construction. Nonerodible material shall be used for the construction of causeways and cofferdams. Earthen fill may be used for these structures if armored by nonerodible cover materials. N/A
- 13. When a live watercourse must be crossed by construction vehicles more than twice in any six—month period, a temporary vehicular stream crossing constructed of nonerodible material shall be provided. N/A
- 14. All applicable federal, state and local chapters pertaining to working in or crossing live watercourses shall be met. N/A
- 15. The bed and banks of a watercourse shall be stabilized immediately after work in the watercourse is completed. N/A
- 16. Underground utility lines shall be installed in accordance with the following standards in addition to other applicable criteria:
- 16.1. a. No more than 500 linear feet of trench may be opened at one time. N/A
- 16.2. b. Excavated material shall be placed on the uphill side of trenches. N/A
- 16.3. c. Effluent from dewatering operations shall be filtered or passed through an approved sediment trapping device, or both, and discharged in a manner that does not adversely affect flowing streams or off-site property. N/A
- 16.4. d. Material used for backfilling trenches shall be properly compacted in order to minimize erosion and promote stabilization. <u>N/A</u>
- 16.5. e. Restabilization shall be accomplished in accordance with this chapter. N/A
- 16.6. f. Applicable safety chapters shall be complied with. N/A
- 17. Where construction vehicle access routes intersect paved or public roads, provisions shall be made to minimize the transport of sediment by vehicular tracking onto the paved surface. Where sediment is transported onto a paved or public road surface, the road surface shall be cleaned thoroughly at the end of each day. Sediment shall be removed from the roads by shoveling or sweeping and transported to a sediment control disposal area. Street washing shall be allowed only after sediment is removed in this manner. This provision shall apply to individual development lots as well as to larger land-disturbing activities. N/A
- 18. All temporary erosion and sediment control measures shall be removed within 30 days after final site stabilization or after the temporary measures are no longer needed, unless otherwise authorized by the local program authority. Trapped sediment and the disturbed soil areas resulting from the disposition of temporary measures shall be permanently stabilized to prevent further erosion and sedimentation. N/A
- 19. Properties and waterways downstream from development sites shall be protected from sediment deposition, erosion and damage due to increases in volume, velocity and peak flow rate of stormwater runoff for the stated frequency storm of 24-hour duration in accordance with the following standards and criteria: N/A
- 19.1. a. Concentrated stormwater runoff leaving a development site shall be discharged directly into an adequate natural or man-made receiving channel, pipe or storm sewer system. For those sites where runoff is discharged into a pipe or pipe system, downstream stability analyses at the outfall of the pipe or pipe system shall be performed. 19.2. b. Adequacy of all channels and pipes shall be verified in the following manner: N/A
- 19.2.1. (1) The applicant shall demonstrate that the total drainage area to the point of analysis within the channel is one hundred times greater than the contributing drainage area of the project in question; or N/A
- 19.2.2.1. (a) Natural channels shall be analyzed by the use of a two-year storm to verify that stormwater will not
- 19.2.2.2. (b) All previously constructed man-made channels shall be analyzed by the use of a ten-year storm to verify that stormwater will not overtop its banks and by the use of a two-year storm to demonstrate that stormwater will not cause erosion of channel bed or banks; and N/A
- 19.2.2.3. (c) Pipes and storm sewer systems shall be analyzed by the use of a ten-year storm to verify that stormwater will be contained within the pipe or system. N/A
- 19.3. c. If existing natural receiving channels or previously constructed man—made channels or pipes are not adequate, the applicant shall: <u>N/A</u>
- 19.3.1. (1) Improve the channels to a condition where a ten-year storm will not overtop the banks and a two-year storm will not cause erosion to channel the bed or banks; or N/A
- 19.3.2. (2) Improve the pipe or pipe system to a condition where the ten-year storm is contained within the appurtenances; N/A 19.3.3. (3) Develop a site design that will not cause the pre-development peak runoff rate from a two-year storm to
- increase when runoff outfalls into a natural channel or will not cause the pre-development peak runoff rate from a ten-year storm to increase when runoff outfalls into a man-made channel; or N/A 19.3.4. (4) Provide a combination of channel improvement, stormwater detention or other measures which is
- satisfactory to the plan approving authority to prevent downstream erosion. N/A

overtop channel banks nor cause erosion of channel bed or banks. N/A

- 19.4. d. The applicant shall provide evidence of permission to make the improvements. N/A
- 19.5. e. All hydrologic analyses shall be based on the existing watershed characteristics and the ultimate development condition of the subject project. N/A
- 19.6. f. If the applicant chooses an option that includes stormwater detention, he shall obtain approval from the locality of a plan for maintenance of the detention facilities. The plan shall set forth the maintenance requirements of the facility and the person responsible for performing the maintenance. N/A
- 19.7. a. Outfall from a detention facility shall be discharged to a receiving channel, and energy dissipators shall be placed at the outfall of all detention facilities as necessary to provide a stabilized transition from the facility to the receiving channel. <u>N/A</u>
- 19.8. h. All on—site channels must be verified to be adequate. N/A
- 19.9. i. Increased volumes of sheet flows that may cause erosion or sedimentation on adjacent property shall be diverted to a stable outlet, adequate channel, pipe or pipe system, or to a detention facility. N/A
- 19.10. j. In applying these stormwater management criteria, individual lots or parcels in a residential, commercial or industrial development shall not be considered to be separate development projects. Instead, the development, as a whole, shall be considered to be a single development project. Hydrologic parameters that reflect the ultimate development condition shall be used in all engineering calculations. N/A
- 19.11.k. All measures used to protect properties and waterways shall be employed in a manner which minimizes impacts on the physical, chemical and biological integrity of rivers, streams and other waters of the state. N/A

TABLE 6-1 GENERAL EROSION AND SEDIMENT CONTROL NOTES

Unless otherwise indicated, all vegetative and structural erosion and sediment control practices will be constructed and maintained according to minimum standards and specifications of the Virginia Erosion and Sediment Control Handbook and Virginia Regulations VR 625-02-00 Erosion and Sediment Control Regulations.

ES-2N/A

All erosion and sediment control measures are to be placed prior to or as the first step in clearing.

ES-4

A copy of the approved erosion and sediment control plan shall be maintained on the site at all times.

ES-5Prior to commencing land disturbing activities in areas other than indicated on these plans (including, but not limited to, off—site borrow or waste areas), the contractor shall submit a supplementary erosion control plan to the owner for review and approving authority.

The contractor is responsible for installation of any additional erosion control measures necessary to prevent erosion and sedimentation as determined by the plan approving authority.

All disturbed areas are to drain to approved sediment control measures at all times during land disturbing activities and during site development until final

ES-8 N/A

stabilization is achieved.

The contractor shall inspect all erosion control measures periodically and after each runoff-producing rainfall event. Any necessary repairs or cleanup to maintain the effectiveness of the erosion control devices shall be made immediately.

E&S LEGEND

(CE) 3.02 CONSTRUCTION ENTRANCE

(DD) 3.09 TEMPORARY DIVERSION DIKE

(CRS) 3.03 CONSTRUCTION ROAD STABILIZATION

(RWD) 3.11 TEMPORARY RIGHT-OF-WAY DIVERSION

3.14 TEMPORARY SEDIMENT BASIN

3.17 STORMWATER CONVEYANCE CHANNEL

(BM) 3.36 SOIL STABILIZATION BLANKETS AND MATTING

(TP) 3.38 TREE PRESERVATION AND PROTECTION

(SAF) 3.01 SAFETY FENCE

SF) 3.05 SILT FENCE

(IP) 3.07 INLET PROTECTION

OP 3.18 OUTLET PROTECTION

(SR) 3.29 SURFACE ROUGHING

(TS) 3.31 TEMPORARY SEEDING

(PS) 3.32 PERMANENT SEEDING


3.35 MULCHING

ے

22 22








Ш 里 ACE BUILI REPL AND ACAD 23 GII Щ \bigcirc Ĭ E

0


 $\sum_{i=1}^{n} \sum_{j=1}^{n} a_{ij}$



Drawn By

RCW Checked By Project Date 08/26/14 Drawing 4228

Commission No.



REMOVE AND REPLACE THE FRONT FACADE OF BUILDING
623 GILMER AVE. NW
ROANOKE, VIRGINIA

102 Albemarle Ave. Roanoke, Virginia 24013

P.C.

Z

No. Date Description

By MEREDITH, JR

Drawn By SAC


Checked By DRM

Date 08/26/14

Drawing 4228


Commission No. 4228

C-1Sheet 4 of 8




NORTH ELEVATION

1/4"=1'-0" SCALE



EAST ELEVATION

1/4"=1'-0" SCALE



- PILASTERS (TYP) TRUSSES (TYP) -SINGLE STORY CMU BUILDING ROOF SECTION (SEE NOTE #1) RAFTERS (SEE NOTE #5) GROUND LEVEL EXISTING CULVERT ELECTRICAL BOX (REMOVE) - BELOW GROUND EXISTING CULVERT GILMER AVENUE N.W.

DEMOLITION NOTES

- ROLL RUBBER ROOF BACK FOR LATER RE-INSTALLATION.

- REMOVE AND DISPOSE OF RAFTERS.

DEMOLITION PLAN

1/8"=1'-0" SCALE

CAREFULLY REMOVE ROLL-UP DOOR, FRAME, HARDWARE FOR RE-INSTALLATION

CAREFULLY REMOVE PEDESTRIAN DOOR, HARDWARE AND FRAME FOR RE-INSTALLATION.

REMOVE AND DISPOSE OF DOWNSPOUT.

Drawn By Checked By Date 08/26/14 Drawing Commission No.


Lic No.22942

102 Albemarle Ave. Roanoke, Virginia 24013

P.C.


REMOVE AND REPLACE THE FRONT FACADE OF BUILDING
623 GILMER AVE. NW
ROANOKE, VIRGINIA

www.lmwpc.net ph: 540.345.0675 fax: 540.342.4456 Imwena@lmwnc.net



WEST ELEVATION

1/4"=1'-0" SCALE



2'-0"

- 66**'-51"** -

WEST ELEVATION

1/4"=1'-0" SCALE

102 Albemarle Ave. Roanoke, Virginia 24013

P.C.

FRONT

E AND REPLA REMOVE

DOUGLAS R. MEREDITH, JR Lic No.22942

Drawn By Checked By 08/26/14

4228 Drawing Commission No.

