




2 SF-1
1/4" = 1'-0"



3 SF-2
1/4" = 1'-0"



4 SF-3
1/4" = 1'-0"



5 STOREFRONT DOOR ELEVATION
1/4" = 1'-0"



6 LIGHT FIXTURE 1

OLD AGE INDOOR/OUTDOOR LED BARN LIGHT, 18" SHADE WIDTH, 6-1/2" SHADE HEIGHT, STYLE NUMBER (22) CONTEMPORARY STEM STYLE, BLACK STEM FINISH, SHADE AND BASE COLOR TO BE DETERMINED FROM MANUFACTURERS FULL RANGE, WWW.COCOWEB.COM, OR APPROVED EQUAL.



7 LIGHT FIXTURE 2

OUTDOOR NORTHWESTERN 6" GLOBE WHITE GLASS FIXTURE, MODEL NUMBER OP-8876-14-6, 1'-2" SHADE WIDTH, 8-1/2" SHADE HEIGHT, WWW.SCHOOLHOUSEELECTRIC.COM OR APPROVED EQUAL.

NOTE: REPOINT CRACKED AND DETERIORATED MORTAR JOINTS ON THE WEST WALL UNDER THE UNIT PRICE PROVISIONS OF THE CONTRACT.

SIGN BY OWNER MAINTAIN EXISTING SIGNAGE

NEW ALUMINUM STOREFRONT WINDOWS, MATCH EXISTING FENESTRATION

NEW 4X4 CERAMIC TILE, TYP MAINTAIN EXISTING VENTS ON BOTH SIDES OF FACADE

STAINLESS STEEL SCHLUTER STRIP FULL HEIGHT OF TILE, TYP AT CORNERS

NEW STOREFRONT DOORS, TRANSOMS AND THRESHOLD TO REPLACE EXISTING IN SAME LOCATION, TYP

MODIFY EXISTING STOREFRONT LAYOUT AS REQUIRED TO ACCOMMODATE NEW 3'-0" WIDE DOORS

PATCH AND REPAIR TERRAZZO ENTRANCE FLOORING

1 SOUTH ELEVATION
1/4" = 1'-0"

CONTRACTOR TO VERIFY ALL DIMENSIONS IN FIELD




NEW LIGHT FIXTURE (5) SOUTH ELEVATION SEE 6/A201, TYP

REPLACE NEW LIGHT FIXTURE AT ENTRANCE (2 TOTAL), SEE 7/201, TYP

PROVIDE NEW METAL COPING OVER THE EXISTING CAST-IN-PLACE CONCRETE COPING. NEW COPING SHALL BE FASTENED TO THE EXISTING COPING WITH A METAL CLEAT. NEW COPING SHALL EXTEND A MINIMUM OF 1 INCH OVER THE EXISTING COPING BED JOINT AT THE EXTERIOR FACE AND A MINIMUM OF 1 INCH OVER THE TOP EDGE OF THE MEMBRANE ROOFING ON THE INSIDE FACE OF THE PARAPET. TYPICAL AT ALL FOUR SIDES.

NOTES:
1. CLEAN EXISTING BRICK ON SOUTH (FRONT) ELEVATION.
2. REPOINT CRACKED AND DETERIORATED MORTAR JOINTS UNDER THE UNIT PRICE PROVISIONS OF THE CONTRACT.

PROVIDE NEW EXTERIOR GRADE GWS CEILING, PAINT



10 CHURCH AVE SE, PLAZA SUITE 1 ROANOKE, VIRGINIA 24011 540.342.60

CITY OF ROANOKE

FACADE IMPROVEMENT PROGRAM

SPECTRUM DESIGN PROJECT NO. 14120



DATE: 22 JANUARY 2016
DESIGN ARCHITECT: LWK
PROJECT ARCHITECT: LWK
PROJECT ENGINEER: DCV
CHECKED BY: KES
DRAWN BY: KES
REVISIONS: NUMBER DATE

SHEET TITLE

1205 PATTERSON AVE S
SOUTH ELEVATION

A201