

**Connection of Garden City Greenway to Roanoke River Greenway
ITB# 16-06-01**

Pre Bid Notes

The Project Manual was reviewed by the Project Manager.

An addendum will be issued, which will include a revised bid form. Micropile testing will be omitted from the bid form and the specifications (Section 02450) will be updated.

Prefabricated Pedestrian Bridge suppliers have been identified under Section 05200. Note that bidders are not restricted to the designated suppliers. Bridge Manufacturers must comply with the specifications outlined in this Section. Other manufacturers will be considered provided they comply with the required specifications. Suppliers listed are not intended to restrict competition.

Note that the plans attached are conceptual and that field measurements for the span length of the bridge will be provided by the Contractor during construction.

The City has access to a WVWA easement at the site which may be used as a staging area.

A different site was originally considered for placement of the bridge. The site has changed. Geotechnical study was performed at the prior site, which is adjacent to current site. Contractors should expect to drill down for at least 30 feet to find competent rock.

Traffic plan is included in the drawings. Contractor will be responsible for necessary traffic control.

Note the requirement for curb ramp detectible warning. The City requires cast iron and the warning must extend the full width of the ramp- 8'.

Contractor is responsible for coordinating utilities as necessary. Coordination utilities is included as a lump sum bid item on the Revised Bid Form.

See Questions and Answers.