

ITB# 15-10-06
13TH STREET STREESCAPE PROJECT WEST END TARGET AREA
QUESTIONS & ANSWERS

Q: What type of video detection will the City be providing for the traffic signal?

A: **Iteris, Contact RGA, LLC for information on this product - it is a City Standard.**

Q: What type of radio system will the City be providing for the traffic signal?

A: **Encom Radio 5200 for more information contact RGA, LLC**

Q: The provisions specify "antennas" so are there two at this intersection?

A: **No, there is one and the City provides the antenna**

Q: In the Lump Sum scope of work for the traffic signal is mentions directional bored. If the conduit is bored there will not be flowable backfill? Which do you prefer?

A: **Directional boring is not a requirement. All work can be achieved with open trench. It is at that Contractor's discretion if they choose to directional bore to avoid impacts to traffic.**

Q: Is directional boring allowed for the lighting also? If so, there will not be flowable backfill included.

A: **Lighting conduit will be open trench.**

Q: The documents specify power supply/service as lump sum for the lighting and traffic signal. If the poles and wiring are to be installed by others, would someone else not provide the service?

A: **AEP provides the poles and wiring however the contractor is responsible for running the conduit, pulling string to the service point. AEP will make the connections.**

Q: Is the controller & cabinet provided by the City going to be new or use existing? Also, what type of controller & cabinet will be installed?

A: **Brand new. Eagle Controller and cabinet.**